

KAVERI GRAMEENA BANK

(Established by - Govt of India: Sponsored by - State Bank of Mysore)

HEAD OFFICE

CA 20, VIJAYANAGARA 2nd STAGE

MYSURU

KGB/STY DEPT.

Date:25/07/2016

NOTICE INVITING TENDER

**Interior Furnishing work at KGB Vijayanagara 4th stage Branch,
Mysuru Region.**

NOTE:

Bank invites sealed quotations from **empanelled Interior Furnishers** to carry out Interior Furnishing work at KGB Vijayanagara 4th stage Branch of Mysuru Region. The empanelled Interior Furnishers may send sealed quotations to Kaveri Grameena Bank, Head Office, Mysuru.

Starting Date of Tender: 25/07/2016

Closing Date of Tender: 03/08/2016

Sd/-

Senior Manager (Sty and Fur)

Place: Mysuru

Date: 25/07/2016

Note :

1. All Rates shall be inclusive of all Taxes Income/sales Tax etc.,
2. The Rates should also be inclusive of the cost of disposal of debris Generated out of the work site by transportation.
3. Tenders should Ascertain the scope of work and quality of the Item before starting the work and the materials used should be as per the list enclosed.
4. The tax deduction at source : Income tax and sales tax as applicable will be deducted at source out of the bill amount payable to the contractor.

KAVERI GRAMEENA BANK HEAD OFFICE MYSORE

SCHEDULE FOR INTERIOR WORKS AT KGB VIJAYANAGAR 4TH STAGE BRANCH.

Page - 1

Sl.No	ITEMS DISCRPTION	Qty	Unit	Rate	Amount
1	CASH COUNTER : Providing and fixing of cash counter having size of 2'6"hx2'6"wx5'0"L, assembly made out of 19mm commercial board and with drawer cum cabinet unit with shutter , key board drawers, cable hole with PVC cap, foot rest, etc, all the exposed edges will have T.W.beadings of 0.75"x1.25" with polish. The drawer cum cabinet unit should be provided in the counters with minimum length of 4'0" of counters. as per the following specifications. a) Providing counter top 15" wide to be fixed for entire length at 3'9" level made out of 19mm commercial board of approved make and a slit opening of 1'6"x6" size with 4mm thick plain glass shall be provided in the counter top. b) The drawers (2Nos.) and the cabinet unit to be made out of 19mm commercial board as per standard design with spring hinges. c) Providing pigeon hole unit of approved size & design made out of 12mm pre-laminated board properly placed in between counter top and customer top including painting /polishing etc, complete as required. d) providing and fixing 1mm thick laminate of approved make and colour using suitable adhesives in all the visible/exposed portions of the counter / drawer/cabinet /key board and all the inner /non visible surfaces, including under side of the counter to be painted with synthetic enamel (two coats) over a coat of wood primer, size 0.75"x 1.25" / lippings/ TW beading duly polished including the cost of all required hardware fittings, ball catches handles piano hinges etc, as specified, in the drawing.The laminate and granite of gang saw cut to be used as per the approve design of the bank.	5	Rft		
a	Providing and fixing 10/12mm thick glass to the top of the counters with edge polishing to counter top after pasting laminated sheet to counter top or 20mm thick granite top	15	sft		
b	Design band of 12mm ply and lamination with brass / S.Steel. stud in front of the counter	8	rft		
c	Providing and making 2.5" hole on Granite/glass top of the counter	1	No		
d	Providing and fixing godrej / Ebco M.P. locks to counter drawer and cabinet	4	Nos		
2	CLERICLE COUNTER/BANKING COUNTER : Providing and fixing of banking counter comprising of 4'0" length each and 32"wide x30"ht clerical top but the rest same as in item for cash counter having all specifications including providing sliding key board drawer 2'x1'6" with 19mm commercial ply/board and T.W.frame work with sliding channels/stopping arrangements, but with following specification. a) Without pigeon hole racks, & slit opening but with cabinet unit as an integral part as per cash counter specification. (customer,s top to be provided with 12 mm thick glass with etching on borders with polishing to be provided vertically with support of wooden pillars, as per the drawing enclosed.	21	Rft		
a	Providing and fixing 10/12mm thick glass to the top of the counters with edge polishing to counter top after pasting laminated sheet to counter top or 20mm thick granite top	63	sft		
b	Design band of 12mm ply and lamination with brass / S.Steel stud in front of the counter on design band	30	rft		
c	providing and fixing godrej/Ebco M.P. locks	25	Nos		
d	<u>providing and making 2.5" hole on granite/glass top</u>	4	Nos		
3	WICKET GATE : Providing and fixing wicket gate in level with counter height using 19mm block board of approved make fixing it to the counter by required frame work of teak wood, exposed surface to be pasted with 1.2mm thick laminate, with required lipping on edges of board, and polishing of teak wood frame work, including all hard wares etc. complete.(with counter side partition)	15	sft		

KAVERI GRAMEENA BANK HEAD OFFICE MYSORE
SCHEDULE FOR INTERIOR WORKS AT KGB VIJAYANAGAR 4TH STAGE BRANCH.

page - 2

Sl.No	ITEMS DISCRPTION	Qty	Unit	Rate	Amount
4	MANAGER'S CABIN : 5' HT. WOODEN PARTLY GLAZED PARTITION : Providing and fixing low height partition in level with counter height using 2" x 2" sal wood frame / 2"x2" Aluminium section frame with 6mm commercial ply on either side, fixing it to the counter / partition frame, both exposed surface to be pasted with 1.0 mm thick laminate of approved pattern, make & colour including providing 12/10 mm thick plain etched glass panel for 5'ht partitions and 6mm glass for 7'ht and above partitions to be used. 3.5" x 0.75" beech wood beading on top edge of panel with polish & melamine spray including all hardwares etc, complete. The quoted rate should include providing and fixing 5' ht. door shutters with glass panel with double line etching on borders, with locks, brass handles and hinges wherever necessary with all hardware accessories. The design and specification should be as per the enclosed drawing.				B/F
		265	sft		
a	Door lock for Manager's cabin's door	2	Nos		
b	partition for officers / server /UPS / others	40	sft		
c	For storage purpose Atta covering with laminated shutters	0	sft		
d	Main Entrance door	85	sft		
e	Floor spring 2Nos	2	Nos		
5	CASH CABIN : As per the specification of item No 4 and drawing (5' ht.)	110	sft		
b	Door lock for cash cabin door 1 No.	1	No		
6	CUSTOMER'S BENCH WITH BACK: Providing and placing of multi seater (3 seater) made with CR hollow section for frame work and CR perforated sheet with powder coated for seat, back and frame work.				-NIL-
7	CHEQUE WRITING TABLE WITH SUGGESTION BOX AND CHEQUE DROP BOX (Three in one) : Providing and placing in position of table made out of 40x40mmx14g of MS square hollow section for frame works with slope towards customer's side, of size 3.5'back/3.25'front ht.x3'w x 1.75'depth. The top of the table is made out of 3'x1.75'x19mm commercial block board pasted with 1.5mm laminate with suitable adhesive, with all round beach wood beadings with melamine polishing for beadings, with painting with 2 coats of metal primer and two coats of duco spray painting to metallic surfaces and 2 coats of wood primer with enamel paint for invisible surfaces of plywood as per drawing enclosed	1	No		
8	Notice display board : Providing and fixing Notice board of size 4' x 2' made with good quality hard wood for frame work and 12mm thick soft board and fabric of approved colour with necessary hooks for suspending with all exposed surfaces neatly finished with melamine polish including fixing necessary T.W. / B.W. beadings duly polished.	8	sft		
9	Working hours board: Providing and fixing working hours board of 2' x 1.5' size, made with 12mm thick commercial ply pasted with 1mm thick laminate of approved make and colour, with all round T>W>/ B>W. beadings including melamine polish and suspending hooks and fixing on wall at required place.	1	No		

KAVERI GRAMEENA BANK HEAD OFFICE MYSORE
SCHEDULE FOR INTERIOR WORKS AT KGB VIJAYANAGAR 4TH STAGE BRANCH.

Page - 3

Sl.No	ITEMS DISCRPTION	Qty	Unit	Rate	Amount
10	FALSE CEILING: a Providing and fixing Armstrong make false ceiling tiles 2'x2' finished as above	0	sft		
				B/F	
10	SIDE TABLE WITH PROJECTION: Providing and placing of side table made out of 25x25mmx14g MS square hollow section for vertical and horizontal frames with synthetic enamel and metal primer of size: (2.75'x16"x2.5'ht.) with top and middle shelf. The top and shelf of the side table is made out of 2.5'x1"x19 mm commercial block board pasted with 1.2 mm laminate of approved make and shade with alround TW beadings with polishing ,on 25x25mm hollow section, the under side of the boards to be painted with wood primer and synthetic enamel of approved make, with 9" projection above table top to rest the ledgers, (with extention up-wards of leg sections.) for printer	1	No		
	SERVER TABLE (3' X 1.75' X 2.5')	1	No		
11	SIDE TABLE WITHOUT PROJECTION: made as per the specification of item of side table with projection , but without extension of the legs up-wards.				-NIL-
12	STORAGE UNIT CABINET TYPE : Providing and fixing storage systems of 1.5' depth of required length and height of the cabinet made with 18mm commercial board of approved make with ISI, mark. The top sides and front face of the cabinet have to be pasted with 1mm thick laminated sheet. The cabinet should have required Nos. of shelves / with doors fitted with good quality hinges and locking arrangements, with magnet catch. For rack type storage units more Nos of shelves and partitions to be provided. All the edges of the cabinet should be provided with T.W. / beech wood beadings with two coats of melamine polish and inner surfaces / and the back side of the cabinet have to be painted with 2 coats of wood primer and two coats of enamel painting of approved colour and make of the paints. The colour of the laminated sheet , handles and other hardware items have to be used as per the bank's approved list of materials / bank's prior approval.				
		100	sft		
13	MANAGER'S/Officer's TABLE: Manager's table, made with 19mm commercial board of specified make. The external or visible surface of the table top,front and sides has to be pasted with 1 mm laminated sheet of beach wood colour. The table shall be provided with two drawers cum cupboard with locking arrangements. All the edges of the table shall be provided with beach wood beading of 22mmx6mm/average in size, with melamine polish, and all the invisible surface and under side of the table has to be painted with one coat of wood primer and two coats of enamel paint. The necessary hardware fittings of good quality such as hinges, handles and drawer sliding channels to be neatly fixed for drawers . The size and the design should be as per the specification and drawing. (SIZE: 5'X2.5'X2.5' with key-board & tray for CPU unit)	1	No		
			sft		
14	WALL / PILLAR PANELLING with 12mm PLY/6mm ply with saal wood reeper of 2"x1" section at 2' horizontal /2'vertical supportspasted with 1mm laminate sheet	216	sft		
15	Texture paint	30	sft		

Contractor's signature with seal

Total Rs.

