



# KAVERI GRAMEENA BANK

(Established by - Govt of India: Sponsored by - State Bank of Mysore)

HEAD OFFICE

CA 20, VIJAYANAGARA 2<sup>nd</sup> STAGE

MYSURU

---

KGB/STY DEPT.

Date:08/03/2017

## NOTICE INVITING TENDER

Interior Furnishing work at KGB Huskur and Ramanagara Branch ,  
Bengaluru Region.

### NOTE:

Bank invites sealed quotations from **empanelled Interior Furnishers** to carry out Interior Furnishing work at KGB Huskur and Ramanagara Branch of Bengaluru Region. The empanelled Interior Furnishers may send sealed quotations to Kaveri Grameena Bank, Head Office, Mysuru.

Starting Date of Tender: 08/03/2017

Closing Date of Tender: 17/03/2017

Sd/-

Senior Manager (Sty and Fur)

Place: Mysuru

Date: 08/03/2017

KAVERI GRAMEENA BANK REGIONAL OFFICE  
BANGALORE

**SCHEDULE FOR INTERIOR WORKS AT K.G.B RAMANAGARA BRANCH**

SL	Items Description	Qty/qty	Rate	Amount
1.	<p><b>CASH COUNTER</b> :Providing and fixing of cash counter having size of 5'0"h x 3'.0"w x 7'0" L. assembly with 12mm front &amp; Horizontal glass separately made out of 19mm commercial board and with drawer cum cabinet unit with shutter key board drawers, cable hole with PVC cap foot rest etc., all the exposed edges will have TW beadings of 0.75" and 1.25" with polish. The drawer cum cabinet unit should be provided in the counters with minimum length of 4'0"of counters as per following specification</p> <p>5. Providing counter top 15"00 wide to be fixed for entire length at 3"9" level made out of 19mm commercial board of approved make and a slit Opening of 1'6" x 6" size with 4 mm thick plain glass shall be provided in the corner top.</p> <p>6. The drawers (2 Nos) and the cabinet unit to be made out of 19mm commercial board as per standard design with spring hinges</p> <p>7. Providing pigeon hole unit of approved size &amp; design made out of 12mm pre-laminated board properly placed in between counter top and customer top including painting/polishing etc. complete as required.</p> <p>d) Providing and fixing 1.5mm thick laminate of approved make and colour using suitable adhesives in all the visible/exposed portion of the counter /drawer/cabinet/key board and all the inner /non visible surfaces including underside of the counter to be painted with synthetic enamel 2 coats over a coat of wood primer size 0.75" x 1.25"/lippings/TW beading duly polished including the cost of all required hardware fittings, ball catches, handles piano hinges etc. specified in the drawing.</p> <p>i) Providing and fixing 20mm thick granite to the top of the counters with bull nosing and edge polishing.</p> <p>ii) Design band of 12mm ply and lamination with brass/stainless steel stud in front of the counter.</p> <p>ii) Providing and making 2.5" hole on granite top of the counter</p> <p>iv) Providing and fixing godrej M.P. locks to counter drawer and cabinet</p>	<p>5 Rft</p> <p>15 sft</p> <p>5 sft</p> <p>1 No</p> <p>2 No's</p>		

02	<p><b>CLERICAL/ADVANCE COUNTER</b> :Providing and fixing of clerical counter having size of 4’0” L each and 3’ wide clerical top but the rest same as in item for cash counter having all specifications including providing sliding key board drawer 2’ x 1’6” with 19mm commercial ply and TW frame work with sliding channels/stopping arrangements but with following specifications.</p> <p>a) without pigeon hole racks, and slit opening but with cabinet unit as an integral part as per cash counter specifications. (customers top to be provided with 12 mm thick glass with etching on borders with polishing to be provided vertically with support of wooden pillars, as per the drawing enclosed.</p> <p>i) Providing and fixing 20mm thick granite to the top of the counters with bull nosing and edge polishing.</p> <p>ii) Design band of 12mm ply and lamination with brass/stainless steel stud in front of the counter.</p> <p>ii) Providing and making 2.5” hole on granite top of the counter</p> <p>iv) Providing and fixing godrej M.P. locks to counter drawer and cabinet</p>	18 Rft  54 sft  18 sft  4 No’s  4 No’s		
03	<p><b>WICKET GATE WITH ADVANCE MANAGER PARTITION</b></p> <p>Providing and fixing wicket gate in level with counter height using 19mm block board of approved make fixing it to the counter by required frame work of teak wood. Exposed surface to be pasted with 1.2mm thick laminate with required lipping on edges of board and polishing of teak wood frame work including all hard wares etc. complete (with counter side partition).</p> <p>a) Wicket gate</p>	9 sft		
04	<p><b>MANAGER’S CABIN : 5’ HT WOODEN PARTLY GLAZED PARTITION :</b></p> <p>Providing and fixing flow height partition in level with counter height using 2” x 2” sal wood frame with 6mm commercial ply on either side, fixing it to the counter / partition frame both exposed surface to be pasted with 1 mm thick laminate of approved pattern, make and colour including providing 12 mm thick plain etched glass panel and 3.5” x 0.75” beach wood beading on top edge of panel with polish and melamine spray including all hardwares etc. complete. The quoted rate should include providing and fixing 10’ height door shutters with glass panel with double line etching on borders, with locks, brass handles and hinges wherever necessary with all hardware accessories. The design and specification should be as per enclosed drawing.</p> <p>a) Door lock for managers cabin door</p>	190 sft 2 No’s		

05	<p><b>CASH CABIN :</b> As per the specification of item No.4 and drawing (5' height) with out weld mesh cover to the window inside cash cabin. Including cash room side partition. a) Door lock for cash cabin door - No</p>	120 sft 1 No		
06	<p><b>CHEQUE WRITING TABLE :</b> providing and placing in position of table made out of 40430 mm x 14 gauge of MS square hollow section for frame works with slope towards customers side of size 3.5' back/3.25' front x 3.5' w x 1.75 L top of the table made out of 3.5' x 1.75' x 199mm commercial block board pasted with 1.5mm laminate with suitable adhesive with all round beach wood beading with 2 coats of metal primer and two coats of duco spray painting to metallic surfaces and 2 coats of wood primer with enamel paint for invisible surfaces of plywood, as per specification.</p>	1 No		
07	<p><b>NOTICE DISPLAY BOARD :</b> providing and fixing notice board of size 7'.0" x 2'.6" made with good quality hard wood for frame work and 12mm thick soft board with fabric of approved color with necessary hooks for suspending with all exposed surfaces neatly finished with melamine polish including fixing necessary Teak wood/beach wood beadings duly polished.</p>	17.5 sft		
08	<p><b>WORKING HOURS BOARD :</b> Providing and fixing working hours board of 2' x 1.5' size, made with 12mm thick commercial ply pasted with 1mm thick laminate of approved make and colour with all round teak/beach wood beadings including melamine polish and suspending hooks and fixing on wall all required place.</p>	1 No		
09	<p><b>STORAGE UNIT CABINET TYPE:</b> providing and fixing storage system of 1.5' depth of required length and height of the cabinet made with 19mm block board of approved make with ISI mark. The top, sides &amp; the front face of the cabinet have to be pasted with 1mm thick laminate sheet. The cabinet should have required number of shelves/ drawers with doors fitted with good hinges and godrej locks, with magnet catches. All edges of the cabinet should provided with T.W/B.W beadings with two coats of melamine polish and inner surfaces/and the back side of the cabinet have to be painted with two coats of wood primer and two coats of enamel painting of approved colour make of the paints. The colour of the laminated sheets, PC handles, locks and other hard ware items have to be used as per the banks approved list of materials/bank prior approval. Storage unit for 3' ht</p>	30 sft		

	<p><b>SIDE TABLE FOR SERVER ROOM :</b>  Providing and placing of side table made out of 25 x25 mm x 14 gauge MS sections for vertical and horizontal frames with synthetic enamel and metal primer of size 3'.0" x 1'.9" x 2'.6" With top and middle shelf. The top and shelf of side table is made out of 2.5' x 1" x 19mm commercial block board pasted with 1.2mm laminate of approved make and shade with allround teak wood beading with polishing the under side of the boards to be painted with wood primer and synthetic enamel of approved make.</p>	1 No		
	<p><b>MANAGERS TABLE :</b>  Managers table made with 19mm commercial board of specified make. The externa or visible surface of the table top, front and sides has to be pasted with 1.5 mm laminated sheet of beach wood colour. The table shall be provided with two side drawer cum cabinet units with locking arrangements. All the edges of the table shall be provided with beach wood beading of 22mm x 6mm / average in size with melamine polish, and all the visible surface and under side of the table has to be painted with one coat of wood primer and two coats of enamel paint. The necessary hardware fittings of good quality such as hinges, handle, magnet catches &amp; drawer sliding channels to neatly fixed for drawers. The size and the design should be as per the specification and drawing (SIZE 6' x 2'.9" x 2'.6" with key board and tray for CPU unit).</p>	1 No		

**COLUMN CLADING**

Providing 12mm ply and 1mm laminate with teak wood beading etc.. 65 sft

Total Rs

**Note :-**

1. ALL THE QUOTED RATES SHALL BE INCLUSIVE OFF ALL TAXES (INCOME/SALES TAX )
2. THE QUOTED RATES SHOULD ALSO BE INCLUSIVE OF THE COST OF DISPOSAL OF DEBRIS GENERATED OUT OF THE WORK SITE BY TRANSPORTATION
3. TENDERS SHPOULD ASCERTAIN THE SCOPE OF WORK AND QUALITY OF THE
4. ITEM BEFORE STARTING THE WORK AND THE MATERIALS USED SHOULD BE AS PER THE LIST ENCLOSED.

KAVERI GRAMEENA BANK REGIONAL OFFICE  
BANGALORE

**SCHEDULE FOR INTERIOR WORKS AT K.G.B HUSKURU BRANCH**

	Items Description	Qty/qty	Rate	Amount
01	<p><b>CASH COUNTER</b> :Providing and fixing of cash counter having size of 5'0" h x 3'.0" w x 7'0" L. assembly with 12mm front &amp; Horizontal glass separately made out of 19mm commercial board and with drawer cum cabinet unit with shutter key board drawers, cable hole with PVC cap foot rest etc., all the exposed edges will have TW beadings of 0.75" and 1.25" with polish. The drawer cum cabinet unit should be provided in the counters with minimum length of 4'0" of counters as per following specification</p> <p>a) Providing counter top 15"00 wide to be fixed for entire length at 3"9" level made out of 19mm commercial board of approved make and a slit Opening of 1'6" x 6" size with 4 mm thick plain glass shall be provided in the corner top.</p> <p>b) The drawers (2 Nos) and the cabinet unit to be made out of 19mm commercial board as per standard design with spring hinges</p> <p>c) Providing pigeon hole unit of approved size &amp; design made out of 12mm pre-laminated board properly placed in between counter top and customer top including painting/polishing etc. complete as required.</p> <p>d) Providing and fixing 1.5mm thick laminate of approved make and colour using suitable adhesives in all the visible/exposed portion of the counter /drawer/cabinet/key board and all the inner /non visible surfaces including underside of the counter to be painted with synthetic enamel 2 coats over a coat of wood primer size 0.75" x 1.25"/lippings/TW beading duly polished including the cost of all required hardware fittings, ball catches, handles piano hinges etc. specified in the drawing.</p> <p>i) Providing and fixing 20mm thick granite to the top of the counters with bull nosing and edge polishing.</p> <p>ii) Design band of 12mm ply and lamination with brass/stainless steel stud in front of the counter.</p> <p>ii) Providing and making 2.5" hole on granite top of the counter</p> <p>iv) Providing and fixing godrej M.P. locks to counter drawer and cabinet</p>	<p>5 Rft</p> <p>15 sft</p> <p>5 sft</p> <p>1 No</p> <p>2 No's</p>		

02	<p><b>CLERICAL/ADVANCE COUNTER</b> :Providing and fixing of clerical counter having size of 4'0" L each and 3' wide clerical top but the rest same as in item for cash counter having all specifications including providing sliding key board drawer 2' x 1'6" with 19mm commercial ply and TW frame work with sliding channels/stopping arrangements but with following specifications.</p> <p>a) without pigeon hole racks, and slit opening but with cabinet unit as an integral part as per cash counter specifications. (customers top to be provided with 12 mm thick glass with etching on borders with polishing to be provided vertically with support of wooden pillars, as per the drawing enclosed.</p> <p>i) Providing and fixing 20mm thick granite to the top of the counters with bull nosing and edge polishing.</p> <p>ii) Design band of 12mm ply and lamination with brass/stainless steel stud in front of the counter.</p> <p>ii) Providing and making 2.5" hole on granite top of the counter</p> <p>iv) Providing and fixing godrej M.P. locks to counter drawer and cabinet</p>	17 Rft  51 sft 17 sft 4 No's 4 No's		
03	<p><b>WICKET GATE WITH ADVANCE MANAGER PARTITION</b></p> <p>Providing and fixing wicket gate in level with counter height using 19mm block board of approved make fixing it to the counter by required frame work of teak wood. Exposed surface to be pasted with 1.2mm thick laminate with required lipping on edges of board and polishing of teak wood frame work including all hard wares etc. complete (with counter side partition).</p> <p>a) Wicket gate</p>	15 sft		
04	<p><b>MANAGER'S CABIN : 5' HT WOODEN PARTLY GLAZED PARTITION :</b></p> <p>Providing and fixing flow height partition in level with counter height using 2" x 2" sal wood frame with 6mm commercial ply on either side, fixing it to the counter / partition frame both exposed surface to be pasted with 1 mm thick laminate of approved pattern, make and colour including providing 12 mm thick plain etched glass panel and 3.5" x 0.75" beach wood beading on top edge of panel with polish and melamine spray including all hardwares etc. complete. The quoted rate should include providing and fixing 10' height door shutters with glass panel with double line etching on borders, with locks, brass handles and hinges wherever necessary with all hardware accessories. The design and specification should be as per enclosed drawing.</p> <p>a) Door lock for managers cabin door</p>	106.25 sft 2 No's		
05	<p><b>CASH CABIN :</b> As per the specification of item No.4 and drawing (5' height) with out weld mesh cover to the window inside cash cabin. Including cash room side partition.</p> <p>a) Door lock for cash cabin door - No</p>	85sft 1 No		

06	<p><b>CHEQUE WRITING TABLE :</b> providing and placing in position of table made out of 40x30 mm x 14 gauge of MS square hollow section for frame works with slope towards customers side of size 3.5' back/3.25' front x 3.5' w x 1.75 L top of the table made out of 3.5' x 1.75' x 199mm commercial block board pasted with 1.5mm laminate with suitable adhesive with all round beach wood beading with 2 coats of metal primer and two coats of duco spray painting to metallic surfaces and 2 coats of wood primer with enamel paint for invisible surfaces of plywood, as per specification.</p>	1 No		
07	<p><b>NOTICE DISPLAY BOARD :</b> providing and fixing notice board of size 7'.0" x 2'.6" made with good quality hard wood for frame work and 12mm thick soft board with fabric of approved color with necessary hooks for suspending with all exposed surfaces neatly finished with melamine polish including fixing necessary Teak wood/beach wood beadings duly polished.</p>	17.5 sft		
08	<p><b>WORKING HOURS BOARD :</b> Providing and fixing working hours board of 2' x 1.5' size, made with 12mm thick commercial ply pasted with 1mm thick laminate of approved make and colour with all round teak/beach wood beadings including melamine polish and suspending hooks and fixing on wall all required place.</p>	1 No		
09	<p><b>STORAGE UNIT CABINET TYPE:</b> providing and fixing storage system of 1.5' depth of required length and height of the cabinet made with 19mm block board of approved make with ISI mark. The top, sides &amp; the front face of the cabinet have to be pasted with 1mm thick laminate sheet. The cabinet should have required number of shelves/ drawers with doors fitted with good hinges and godrej locks, with magnet catches. All edges of the cabinet should provided with T.W/B.W beadings with two coats of melamine polish and inner surfaces/and the back side of the cabinet have to be painted with two coats of wood primer and two coats of enamel painting of approved colour make of the paints. The colour of the laminated sheets, PC handles, locks and other hard ware items have to be used as per the banks approved list of materials/bank prior approval. Storage unit for 3' ht</p>	30 sft		
10	<p><b>SIDE TABLE FOR SERVER ROOM :</b> Providing and placing of side table made out of 25 x25 mm x 14 gauge MS sections for vertical and horizontal frames with synthetic enamel and metal primer of size 3'.0" x 1'.9" x 2'.6" With top and middle shelf. The top and shelf of side table is made out of 2.5' x 1" x 19mm commercial block board pasted with 1.2mm laminate of approved make and shade with allround teak wood beading with polishing the under side of the boards to be painted with wood primer and synthetic enamel of approved make.</p>	1 No		



11	<b>MANAGERS TABLE :</b> Managers table made with 19mm commercial board of specified make. The external or visible surface of the table top, front and sides has to be pasted with 1.5 mm laminated sheet of beach wood colour. The table shall be provided with two side drawer cum cabinet units with locking arrangements. All the edges of the table shall be provided with beach wood beading of 22mm x 6mm / average in size with melamine polish, and all the visible surface and under side of the table has to be painted with one coat of wood primer and two coats of enamel paint. The necessary hardware fittings of good quality such as hinges, handle, magnet catches & drawer sliding channels to neatly fixed for drawers. The size and the design should be as per the specification and drawing (SIZE 6' x 2'.9" x 2'.6" with key board and tray for CPU unit).	1 No		
12	<b>COLUMN CLADING</b> Providing 12mm ply and 1mm laminate with teak wood beading etc..	60 sft		
			Total Rs	

**Note :-**

2. ALL THE QUOTED RATES SHALL BE INCLUSIVE OFF ALL TAXES (INCOME/SALES TAX )
3. THE QUOTED RATES SHOULD ALSO BE INCLUSIVE OF THE COST OF DISPOSAL OF DEBRIS GENERATED OUT OF THE WORK SITE BY TRANSPORTATION
4. TENDERS SHPOULD ASCERTAIN THE SCOPE OF WORK AND QUALITY OF THE
5. ITEM BEFORE STARTING THE WORK AND THE MATERIALS USED SHOULD BE AS PER THE LIST ENCLOSED.